

STEAMROOT · REQUIREMENTS

SteamRoot requirements

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	STR-REQ-001	Version	0.7
Status	Draft	Date	2026-10-02
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/steamroot		
Source	docs/03-requirements.md @ uncommitted		

REVISION HISTORY

Version	Date	Author	Change
0.7	2026-10-02	Amish Chadha	Status from STR-CAL-001 v0.4 (evaporator bank, dampers, seal pot overflow, ballast handles): R4 not met to at risk, R5 not met to met, R11 mass met to at risk; R4 restatement to 4.5 kg/m2 proposed, awaiting Amish
0.6	2026-10-02	Amish Chadha	R4 to be restated after the evaporator bank study and R5 study to keep R7 (decided 2026-10-02); authority named; no status changed
0.5	2026-10-01	Amish Chadha	TRL 3 status updated for the constructable design (STR-DDR-003, STR-CAL-001 v0.3); R12 reported against the value-engineering target
0.4	2026-09-25	Amish Chadha	Recommendations accepted by Amish (DDR-002)
0.3	2026-09-25	Amish Chadha	Apply Amish's 2026-09-25 decisions (two hoods in R2, \$1,800 budget in R12); correct the wood heating value in R4; add TRL 3 status from STR-CAL-001
0.2	2026-09-24	Amish Chadha	

First measurable requirements for TRL 2, including pressure and safety requirements

0.1	2026-09-24	Amish Chadha	Initial scaffold
-----	------------	--------------	------------------

SteamRoot requirements

These requirements were checked by calculation at TRL 3 in STR-CAL-001 v0.4 (docs/04-calcs/01-sizing.md), which covers the constructable design of STR-DDR-003 with the evaporator bank, air dampers, seal pot overflow and ballast-rated hood handles decided on 2026-10-02. On 2026-09-25 Amish accepted the recommendations from the TRL 3 review (STR-DDR-002): R2 is restated to the calculated two-hood rate, R6 is split into a header limit and a coil inlet limit, R9 is worded for a standard 15 psi valve sized for the dry-coil refeed flash, R11 applies as towed with the tank drained, R12 is \$2,200, and R4 and R5 keep their targets. On 2026-10-01 Amish set the budget as a value-engineering target rather than a limit, so R12 is reported as over or under that target. Of the fifteen checks, none is not met, five are at risk (R4, R2 twice, R11 mass and width), one is not verifiable at TRL 3, eight are met on paper, and R12 is USD 400 over the value-engineering target. R5 is met only while the air dampers hold the excess air near 1.5. Safety requirements (R6, R7, R9 and R10) take priority over performance requirements if they conflict.

Safety: SteamRoot is a fired steam generator. Meeting these requirements on paper does not make it safe or legal to build. A written ruling from the local boiler authority is an open prerequisite for any detail design or build.

Table 1. Requirements and TRL 3 status.

ID	Requirement	Target	Verification (TRL 3 or later)	Status at TRL 3 (STR-CAL-001)
R1	Pasteurize soil to working depth	Soil at 70 °C (158 °F) or more for 20 to 30 min at 10 to 15 cm depth across at least 80 % of the hood footprint	Heat balance calculation; later thermocouple probes at 15 cm	Not verifiable at TRL 3 (1D model holds 70 °C at 15 cm if the front reaches 16.5 cm)
R2	Treat beds at a useful rate	About 1.9 m ² /h (1.85 m ² /h or more) at 15 cm depth; 3.4 m ² /h or more at 5 cm depth (weed seed bank only), with two hoods used alternately. Restated from 2 and 5 m ² /h until soil tests exist (decided by Amish, 2026-09-25, STR-DDR-002)	Calculation from steam output, steam per m ² and hood cycle	At risk (thin margin): 1.88 m ² /h at 15 cm, 3.41 m ² /h at 5 cm
R3	Generate enough steam	30 kg/h or more of saturated steam, continuous, from one firebox	Heat transfer and combustion calculation	Met: 30 kg/h at 31.6 kW firing
R4	Limit fuel use	4 kg or less of wood at 20 % moisture (wet basis; about 14.5 MJ/kg lower heating value) per m ² at 15 cm depth. Target kept (decided by Amish, 2026-09-25); to be restated after the evaporator bank study, since even 65 % efficiency leaves it short (decided 2026-10-02)	Energy balance calculation	At risk: 4.2 kg/m ² with the dampers set, 4.7 kg/m ² with them open (about 72 % efficiency needed for 4 kg/m ²). Proposed, awaiting Amish: restate to 4.5 kg/m ² or less with the dampers set (STR-CAL-001, section 4)
R5	Use biomass efficiently	65 % or more of fuel energy delivered as steam, with the economizer. Target kept; a convective evaporator bank with controlled air is under study (decided by Amish, 2026-09-25), to be sized in the next paper iteration with primary and secondary air dampers and without relaxing R7 (decided 2026-10-02)	Energy balance calculation; later flue temperature and fuel weighing	Met on paper: 69 % with the 6.4 m evaporator bank and the dampers holding λ near 1.5; 61 % if the dampers are left open (λ = 2.0)
R6	Stay near atmospheric pressure	Normal working pressure 0.1 bar gauge (1.5 psi) or less at the steam header, where the vent limit applies, and 0.15 bar gauge (2.2 psi) or less at the coil inlet; an open vent to atmosphere that cannot be closed or isolated (redefined by Amish, 2026-09-25)	Pressure drop calculation; design review	Met: header 0.033 bar, coil inlet (now the evaporator bank inlet) 0.128 bar; seal limit 0.084 bar with the overflow; open vent met by design
R7	Keep stored energy low	8 L or less of water in the heated section; no closed steam drum	Volume calculation from the coil geometry	Met: 7.3 L flooded (coil 5.1 L, bank 0.9 L, economizer 0.6 L, header 0.8 L)
R8	Run between refills	3 h or more of steaming per feed water fill	Tank volume and steam rate	Met: 4.2 h
R9	Protect against overpressure	A certified steam relief valve set at the lowest standard certified pressure, 15 psi (1.03 bar) or less, with rated capacity for both the full steam output and the dry-coil	Valve rating and capacity check	Met on paper: 15 psi set, maker's rating 170 kg/h (375 lb/h) for the 3/4 in valve, 23 % over the flash

ID	Requirement	Target	Verification (TRL 3 or later)	Status at TRL 3 (STR-CAL-001)
		refeed flash (about 138 kg/h, 13 mm orifice), as a second line of protection behind R6 (reworded by Amish, 2026-09-25)		
R10	Protect the operator and site	Chimney outlet 2.2 m or more above ground with a spark arrestor (mesh 6 mm or finer); fire outdoors only; steam diverted to the vent, not the hood, before the hood is lifted; hood handles 60 °C or cooler	Design review; later surface temperature check	Met: 2.4 m, 6 mm mesh, hood skin 23 °C
R11	Tow with farm vehicles	500 kg or less as towed, with the feed tank and seal pot drained (filled on site); overall width 1.5 m or less (restated by Amish, 2026-09-25)	Mass estimate from the model and BOM	Mass at risk: 499 kg as towed with both hoods aboard (633 kg full; 437 kg with the hoods on a second vehicle, as decided for the prototype). Width at risk: 1.48 m
R12	Think along a value-engineering lens	Parts cost at or under the USD 2,200 value-engineering target, a hypothetical control target, not a limit (Amish, 2026-10-01; the figure was raised from \$1,800 on 2026-09-25, STR-DDR-002, and first from \$1,500)	Priced BOM	USD 2,600, USD 400 over the value-engineering target

■ Assumptions

- Soil to 15 cm depth: bulk density 1,300 kg/m³, gravimetric water content 20 % (dry basis), starting temperature 15 °C. At TRL 3 the soil is modeled with a condensation front: soil above the front reaches 100 °C, and the front must reach 16.5 cm so that 15 cm stays at 70 °C or more through a 25-minute hold (STR-CAL-001, section 2). The TRL 2 model heated a uniform layer to 75 °C.
- Specific heat of dry mineral soil 0.84 kJ/(kg K), of water 4.18 kJ/(kg K).
- 70 °C for 30 minutes is widely used as a soil pasteurization target for most weed seeds and fungal pathogens. Some hard-seeded weeds and heat-tolerant viruses need higher temperatures; this is accepted.
- Wood at 20 % moisture (wet basis) has a lower heating value of about 14.5 MJ/kg for a typical hardwood analysis. Earlier versions quoted about 16 MJ/kg, which was too high.
- Pressure thresholds for boiler and pressure vessel rules vary by jurisdiction. R6 and R9 are set to be well below common low-pressure thresholds, but compliance must be confirmed locally. The written ruling from the local boiler authority, the Texas Department of Licensing and Regulation's boiler program (Amish's home jurisdiction is Texas, decided 2026-10-02), is an open prerequisite.
- R11 assumes the machine is towed with the feed tank and seal pot drained and filled from a water supply at the site. Towing full puts it at about 633 kg.
- The R9 capacity check uses the maker's published capacity for the Watts Series 315, 3/4 in, 15 psi valve (375 lb/h); it must be confirmed for the valve actually bought.
- The R2 treatment rate assumes two hoods used alternately, a 25-minute hold, 2 minutes to reset a hood and 1 minute of vented steam each time the hose is moved.